

**TIM AVEY STAMPED CONCRETE & SUPPLIES**  
**9534 Main St. Whitmore Lake, Mi. 48189**  
**(734) 449-8294**

**ESTIMATE**

**Estimate Submitted To:**

DDA c/o Dan Smith  
June 7, 2010

**Work To Be Performed At:**

Pat's Hair Salon Main St.  
Whitmore Lake, Mi. 48189

**We hereby propose to furnish all the labor and material necessary for the completion of --- Area #1 ----In front of Pat's Hair Salon – 223 sq. ft. of stamped concrete 4" thick – 6 bag mix w/wire mesh and re-rod – terracotta color – cobblestone pattern w/charcoal release w/clear sealer. No deco drain needed.**

**TOTAL = \$ 2,230.00**

**Fill sand extra**

**Payments to be made as follows:**

**Half down and balance upon completion**

**Not responsible for cracking or landscaping.**

**Respectfully Submitted: Tim Avey**

**Date: June 7, 2010**

**Accepted by: \_\_\_\_\_**

**Date: \_\_\_\_\_**

**TIM AVEY STAMPED CONCRETE & SUPPLIES**  
**9534 Main St. Whitmore Lake, Mi. 48189**  
**(734) 449-8294**

**ESTIMATE**

**Estimate Submitted To:**

DDA c/o Dan Smith  
June 7, 2010

**Work To Be Performed At:**

Margaret & Main St.  
Whitmore Lake, Mi. 48189

**We hereby propose to furnish all the labor and material necessary for the completion of --- Area #2 Margaret and Main St. – 114 sq. ft. stamped concrete 4” thick 6 bag mix w/wire mesh and re-rod terracotta color and cobblestone pattern w/charcoal release and w/clear sealer. Needs Decko Drain**

**TOTAL = \$ 1,140.00**

**Fill sand extra**

**Payments to be made as follows:**

**Half down and balance upon completion**

**Not responsible for cracking or landscaping.**

**Respectfully Submitted: Tim Avey**

**Date: June 7, 2010**

**Accepted by: \_\_\_\_\_**

**Date: \_\_\_\_\_**

**TIM AVEY STAMPED CONCRETE & SUPPLIES**  
**9534 Main St. Whitmore Lake, Mi. 48189**  
**(734) 449-8294**

**ESTIMATE**

**Estimate Submitted To:**

DDA c/o Dan Smith  
June 7, 2010

**Work To Be Performed At:**

Next door to Bowling Alley  
Whitmore Lake, Mi. 48189

**We hereby propose to furnish all the labor and material necessary for the completion of --- Area #3 In front of house next to bowling alley – 494 sq. ft. stamped concrete 4” thick 6 bag mix w/wire mesh and re-rod – terracotta color – cobblestone pattern w/charcoal release & w/clear sealer. Needs new sidewalk due to no drain access.**

STAMPED TOTAL	\$4,940.00
NEW SIDEWALK	<u>\$2,100.00</u>
TOTAL	\$7,040.00

**Fill sand extra**

**Payments to be made as follows:**

**Half down and balance upon completion**

**Not responsible for cracking or landscaping.**

**Respectfully Submitted: Tim Avey**

**Date: June 7, 2010**

**Accepted by: \_\_\_\_\_**

**Date: \_\_\_\_\_**

**TIM AVEY STAMPED CONCRETE & SUPPLIES**  
**9534 Main St. Whitmore Lake, Mi. 48189**  
**(734) 449-8294**

**ESTIMATE**

**Estimate Submitted To:**

DDA c/o Dan Smith  
June 7, 2010

**Work To Be Performed At:**

In front of Bowling Alley  
9455 Main St.  
Whitmore Lake, Mi. 48189

**We hereby propose to furnish all the labor and material necessary for the completion of --- Area #4 In front of bowling alley – 732 sq. ft. stamped concrete 4” thick 6 bag mix w/wire mesh and re-rod - terracotta color, cobblestone pattern w/charcoal release and clear sealer.**

Stamped Concrete Total	\$7,320.00
New sidewalk	<u>\$2,100.00</u>
<b>TOTAL</b>	<b>\$9,420.00</b>

**Fill sand extra**

**Payments to be made as follows:**

**Half down and balance upon completion**

**Not responsible for cracking or landscaping.**

**Respectfully Submitted: Tim Avey**

**Date: June 7, 2010**

**Accepted by: \_\_\_\_\_**

**Date: \_\_\_\_\_**